

GREEN WORLD CHS LTD

REG. NO. T.N.A./(T.N.A.)/HSG(TC)/34537/2021-2022 Dated : 22/03/2022

GUT NO. 242, HISSA NO. 1 TO 7, DIGHE, NAVI MUMBAI - 400 708

Tender Form

Subject- AMC quotation for cleaning service of drainage line & chambers.

Scope of Work :-

Sr.No.	Description	AMC	UOM	Quantity	Quotation (Rs.)
1	<p>The scope of work includes the cleaning of all underground drainage lines and chambers by manual or by using water pressure jet machine as required.</p> <p>In the event of any chamber becomes obstructed during the annual maintenance contract (AMC), cleaning of same to be required & attend within 2 to 4 hours from the intimation. Also weekly inspection is required as part of AMC.</p>	2 Service in year in the interval of 6 month + as and when required for cleaning of drain line and chambers (AMC Comprehensive)	Lump sum	Drainage line & chambers quantity as per below table-1	
Total Rs. =					

1. Phase 1: Access initiation

Commence the cleaning operation by employing specialized equipment to safely open the necessary manholes and access the chambers.

2. Phase 2: Chamber and line sanitation

Utilized high- pressure water jetting in conjunction with manual labour to meticulously cleanse the chamber and connecting drain lines, ensuring the complete removal of debris and buildup.

3. Phase 3: Debris Elimination

Eliminate any residual sand and debris that may have been dislodged during the cleaning process, thereby guaranteeing the complete restoration of flow.

4. Phase 4: Final verification & Closure:

Conclude the operation by conducting a comprehensive inspection to ascertain that all chambers and lines are unobstructed and free of any impediments. Upon successful verification, securely close all manholes and access point.

GREEN WORLD CHS LTD

REG. NO. T.N.A./(T.N.A.)/HSG(TC)/34537/2021-2022 Dated : 22/03/2022

GUT NO. 242, HISSA NO. 1 TO 7, DIGHE, NAVI MUMBAI - 400 708

Table:1 Drainage line & chambers quantity

Sr.No.	Description	UOM	Quantity
a	Sewage Duct & outside chamber	Nos.	69
b	Rain water & kitchen chamber	Nos.	172
c	Manholes	Nos.	37
d	Shop area	Nos.	18
e	Gutter line	Rmt.	600

Safety & Precaution

Worker Safety: We prioritize the safety of all personnel by providing and enforcing the use of appropriate Personal Protective Equipment (PPE), including masks, safety shoes, gloves, and other gear as required for specific tasks and equipment.

Confined Space Procedure: For work inside tanks, chambers, or other confined spaces, we strictly follow confined space entry protocols. This includes the use of ladders, safety harnesses, oxygen masks, gas detectors, and other specialized equipment to ensure worker safety.

Safety & Precautions for Working at Height: We ensure fall protection through the use of guardrails, full-body harnesses, safe scaffolding, and work platforms. All personnel engaged in elevated work must undergo height safety training and perform tasks under supervision.

General Worksite Safety: The company holds full responsibility for implementing and maintaining all necessary safety precautions during work activities, in accordance with established safety standards and regulations.

Terms & Condition

- Society will provide access to water & electricity for cleaning purpose.
- Quarterly Invoice will be raised only.
- The payment due within 15 days of satisfactory completion of the project and the receipt of invoice.
- Any rejection & acceptance in reserved with the Tender Committee.
- In the case of delay to attend call within 4 hours from the intimation, penalty of Rs. 200 per hour to be applicable.

GREEN WORLD CHS LTD


CHAIRMAN


SECRETARY


TREASURER

